nous References

1932
M

Later References

Mul 63-35-2

General and Revenue Secretariat.

Serial Nos 2

Part B for January 1933

SUBJECT

Estimate for Rs 3,800/- for installing a 10 Horse Power pumping unit at the Mydala tank, to ensure a proper flow of water from the tank to the Filter bed at Jumkun

2

The D C Jumkun
" Sany Engineer, R F
" Comptroller
L 5-05-3-5 9 31-1-33

Sanctions the estimate

VW 3 33

ms 27-32-1

OFFICE OF THE PRESIDENT
TOWN MUNICIPAL COUNCIL

2-33

Tumkur Dated 4-1-1933

3084

m

H VENKATARAMIAH QUIET PA BL
President Town Municipal Council
TUMKUR

To

H V Ramaswami, Esquire, M A, B L,

General Secretary to the Government of His Highness
the Maharaja of Mysore, Bangalore

Through -

The Deputy Commissioner,
Tumkur District, Tumkur

Sir

I have the honour to submit, herewith, an estimate amounting to Rs 3800/- received from the Executive Sanitary Engineer, Bangalore -- for installing a 10 H P Pumping Unit at Lydala tank capable of -- pumping about 16,000 gallons of water per hour against a head of 60 ft and to request that sanction of Government may kindly be accorded -- at an early date to enable the work being taken on hand early as the water will not properly flow from the tank to the Filter Bed at -- Tumkur, especially during summer season by means of mear gravitation this difficulty was felt during last summer season and was also -- brought to the notice of Government the Municipal Council have at -- their meeting held on 23-12-1932 sanctioned the estimate in question and a copy of the resolution is also herein enclosed for reference

I, therefore request you to be so good as to obtain the sanction of Government to the resolution of the Municipal Council at a - very early date and also to meet this estimated amount out of the -- closing balance of the Municipality during the current year

6396
1933
TUMKUR DISTRICT

I have the honour to be
Sir,
Your most obedient servant,

H Venkataramiah

President,
Town Municipal Council,
Tumkur

Maintenance Grant — Mudalai Tank

General and Revenue Secretariat | File No 27 of 1932 | [App F III—

Serial No	
	closing balance at the credit of the work is Rs 24,484 minimum balance required to be maintained: Rs 12,307
	Rs CB 18/1/20 The Draft Go is for consideration (Gadgil) Second Member 28/1/33
	by 26-1-33 Case 27/1/33 Draft MSK 27/1/33
2	To the DC, Tumkur, Sanction, R 7, empty Rs 5053-5-0 dy 31-1-33 Sanction the estimate

AN No 5-9-34 3

File No of 193

General and Revenu
Secretariat

ది 12 ఇ 1932 నీ తారీఖు శుక్ర వారమునాడు సాయంకాలము 8 ఘంటలకు శ్రీ మున్సిప్ల్ కార్యాలయమునందు జరిగిన కౌన్సిలు సమావేశములో కౌన్సిలు సభ్యులు క్రింది వారు మాత్రము హాజరు అయ్యిరి -

Present -

1 Mr H Venkataramia, B A , L L , President
2 K Ranga Iyengar , B A , LL B
3 D Rama Rao
4 Rev E C Hoiler
5 Mr R Venkata Rao
6 B Mallappa
7 Desada Yejaman Siddappa
8 A K Sanjeeviah
9 T Venkatappa
10 " Mukam Curappa Setty

The rest were absent

x x

మున్సిపల్ కార్యాలయమునకు సున్నము వేయుటకు ఏర్పాటు చేయుటకు మరియు 10 ఎ ఫ్ ఎ లో కొన్ని కొత్త కాలువలు తవ్వుటకు మరియు సుమారు 3800/ రూపాయలు ఖర్చు అగునట్లు ఏర్పాటు చేయుటకు —

Sanctioned with an

that tenders may also called for

The amount may be met out of closing balance

x x

Sd/- H Venkataramia,
President

COPY

H Venkataramia
President,
Town Municipal Council,
Tumkur

GNR/4/1

Estimate for installing a Pumping Unit at Tumkur, Lydala Tank

4

No	Items of work	Per	Rate	Quantity	Cost
1	One 10 H P Electric Pumping Unit directly coupled-capable of pumping 16,000 gallons per hour against a head of 60 feet with --- starter pipe, connection etc , complete		L S		1000/-
2	Suction pit with a valve-- for the draw off pipe		Do-		600/-
3	Alternative draw off arrange-ment from the existing -- syphon		Do-		800/-
4	A pump shed with a small -- stores 16 x 10		Do-		800/-
5	Erection of pumping unit -- including wiring and lighting etc , complete		Do-		500/-
6	Cart hire, Railway freight and other unforeseen charges		Do-		100/-
				Total Rs	3800/-

Sd/- B R Garudachar,
2-12-1932
Executive Sanitary Engineer
Bureau of Sanitary Engineering
Bangalore

"COPY"

For President,
Town Municipal Council,
Tumkur

G R S App F VI—G 21

SUBJECT

Diary No of letter replied to

Section and —
File No 27-32
Serial No 2

General and Revenue Secretariat
( )
the *193*

Proceedings of the Government of His Highness the Maharaja of Mysore

Date of issue 31/1/ 1933

Signed by Mr MSK

Read— memo No 6396 dy 6-1-33 from the DC, Tumkur on proposal to sanction Rs 3 000 for installing a 10 HP pumping unit at the Jung dada Tank, Order thereon—No the estimated saving balance of the work, also memo no L 5053-5 dy 21/1/33 from the same,

May this be—

(i) printed ?

(ii) treated as a standing order ?

(iii) published in the Gazette, English part ?

( ) translated ?

(v) placed at the disposal of the press ?

(vi) published in the Gazette Kannada part ?

to ensure a further flow of water from the tank to the fields lead at Tumkur during the summer season,

dy com, Tumkur

MSK 23/1

List of Enclosure

Copied by

Examined by

WD 0254—G1 B—10 000—22-8 32

PROCEEDINGS OF THE GOVERNMENT OF HIS HIGHNESS
THE MAHARAJA OF MYSORE

Read —

Memo No 6396 dated 6th January 1933 from the Deputy Commissioner, Tumkur District, forwarding letter No E T 356 of 1932-33 dated 4th/5th January 1933 of the President, Tumkur Town Municipal Council requesting sanction to an estimate for Rs 3,800/- for installing a 10 Horse Power pumping Unit at the Lydala tank, to ensure a proper flow of water from the tank to the Filter bed at Tumkur, during the summer season, the cost being met out of the closing balance of the Municipality

---

Order No L 5053-5/ml 27-32-2

Dated, Bangalore, the 28th/31st January 1933

Sanctioned

M S Krishnamachar
for General Secretary to Government

To

The Deputy Commissioner, Tumkur District
The Sanitary Engineer, Rockefeller, Foundation
The Comptroller to the Government of Mysore